

LEGEND

	EXISTING SURFACE CONTOURS
	BULK EARTHWORKS CONTOURS
	STAGE BOUNDARY
	LOT BOUNDARY
	FUTURE LOT BOUNDARY
	PROPOSED BATTER
	PROPOSED EARTHWORKS CUT
	PROPOSED EARTHWORKS FILL
	EXISTING SURFACE LEVEL FINISHED SURFACE LEVEL

EARTHWORKS NOTES



- FOR GENERAL NOTES REFER TO DRG No. PC2_C01, WHICH IS TO BE REQUESTED AND VIEWED PRIOR TO COMMENCEMENT OF CONSTRUCTION IF NOT SUPPLIED.
- GRASS AND TOPSOIL SHALL BE STRIPPED TO A DEPTH OF 50mm OVER THE EXTENT OF THE WORKS UNLESS DIRECTED OTHERWISE AND STOCKPILED FOR FUTURE USE AS NON-STRUCTURAL FILL IF REQUIRED, OR REMOVE FROM SITE.
- ANY PROPOSED RETAINING WALL WORKS MUST BE WHOLLY WITHIN THE PROPERTY BOUNDARY OF THE SUBJECT SITE, INCLUDING REAR OF RETAINING WALL DRAINAGE INFRASTRUCTURE FOR RETAINING WALLS IN CUT.
- ALL NEW WORKS TO MATCH NEATLY INTO EXISTING
- ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH APPROVED MANAGEMENT PLANS.
- ALLOTMENT & VERGE EARTHWORKS LEVELS SHOWN ARE FINISHED EARTHWORKS SURFACE LEVELS INCLUSIVE OF 100mm TOPSOIL LAYER.
- ROAD FINISHED EARTHWORKS LEVELS ARE TO BOTTOM OF ROAD BOXING.
- CONTRACTOR TO ENSURE SUITABLE EROSION CONTROL MEASURES ARE INSTALLED INCLUDING BUT NOT LIMITED TO SHAKE DOWNS, SILT FENCE ETC.
- PRIOR TO THE CONTRACTOR COMMENCING ANY WORKS DETAILED ON THIS DRAWING, THE CONTRACTOR IS TO NOTIFY ADG ENGINEERS (AUST) PTY LTD AND RECEIVE WRITTEN CONFIRMATION THAT WORKS CAN COMMENCE
- ADEQUATE SAFETY FENCING/BARRIERS TO BE APPLIED TO ALL BATTERS OR RETAINING WALLS (TEMPORARY OR PERMANENT) AS PER RELEVANT AUSTRALIAN STANDARDS AND LEGISLATION.
- DUST CONTROL MEASURES ARE TO INCLUDE SPRAYING WATER ON UNPAVED ROADS, ACCESS TRACKS AND STOCKPILES AT A SUFFICIENT LEVEL TO SUPPRESS DUST GENERATION. ADDITIONALLY CONTRACTORS ARE TO COVER OR ENCLOSE STOCKPILES WHERE REASONABLY PRACTICAL TO RESTRICT DUST MOVEMENT.
- FOR DETAILED GEOTECHNICAL INFORMATION, REFER TO GEOTECHNICAL INVESTIGATION REPORT BY DOUGLAS PARTNERS DATED MARCH 2015. IT IS RECOMMENDED THAT THE GEOTECHNICAL CONSULTANT BE CONTACTED TO CONFIRM THE SOIL CONDITIONS PRIOR TO EARTHWORKS COMMENCING.
- ALL BATTERS AT FRONT OF LOTS TO BE 1 IN 6, UNLESS NOTED OTHERWISE. ALL BATTERS TO REAR AND SIDE BOUNDARIES WITHIN PRIVATE PROPERTIES TO BE 1 IN 2, UNLESS NOTED OTHERWISE.
- CLEARED VEGETATION IS TO BE MULCHED AND STOCKPILED FOR RESPREADING AS DIRECTED BY THE SUPERINTENDENT.
- FOLLOWING THE COMPLETION OF EARTHWORKS THE CONTRACTOR IS TO RESPREAD TOPSOIL AS DIRECTED BY THE SUPERINTENDENT.
- THE CONTRACTOR IS TO LIMIT THE MOVEMENT OF EQUIPMENT AND MANPOWER TO THE MINIMUM AREA NECESSARY FOR EARTHWORKS AND PROTECT ALL VEGETATION OUTSIDE OF THE WORKS BOUNDARY.

PERMISSION TO USE FOR CONSTRUCTION PURPOSES
ROADWORKS AND STORMWATER DRAINAGE

SIGNED _____ DATE _____

DIRECTOR OF TECHNICAL SERVICES - CITY OF PALMERSTON

This permission to use is given on the basis that the Developer and/or Consultant is not absolved from full responsibility for the correctness and accuracy of the design and/or documents associated. This permission is valid for two years from date of signing.



Rev	Date	Description	By	Chk
C	20.07.18	ISSUE FOR APPROVAL	JB	SW
B	25.06.18	ISSUE FOR APPROVAL	JB	SW
A	28.05.18	ISSUE FOR APPROVAL	JB	SW

0 10 20 30m
SCALE 1:500
AT ORIGINAL SIZE (A1)



ADG
Darwin Office
Tenancy 3, Level 1, 5 Edmunds Street,
Darwin, Northern Territory 0800, Australia
GPO Box 2422, Darwin, Northern Territory 0801
T 1300 657 402 F +617 3871 2266
E info@adgce.com W www.adgce.com
BRISBANE / SYDNEY / MELBOURNE / GOLD COAST / SUNSHINE COAST / DARWIN / PERTH

Client
COSTOJIC PTY LTD
Project Name
**ZUCCOLI ASPIRE
PRECINCT C - STAGE 2
CIVIL WORKS**

Discipline CIVIL	Status APPROVAL
Designed By TM	Checked By SW
Project No. 20696	Drawn By JB
The concepts and information contained in this document are the copyright of ADG Engineers (Aust) Pty Ltd. Use or copying of the document in whole or in part without the written permission of ADG Engineers (Aust) Pty Ltd constitutes an infringement of copyright. Do not scale drawings. If in doubt, ask!	

Title EARTHWORKS LAYOUT SHEET 1 OF 2	Drawing No. PC2_C200	Revision C
--	--------------------------------	----------------------