


PROVIDED FOR INFORMATION PURPOSES ONLY SUBJECT TO REGULATORY APPROVALS FROM ALL RELEVANT AUTHORITIES. CHANGES MAY BE MADE WITHOUT NOTICE TO THE WHOLE OR PART OF THE PLANS.



EARTHWORKS NOTES

- FOR GENERAL NOTES REFER TO DRG No. 6A_001, WHICH IS TO BE REQUESTED AND VIEWED PRIOR TO COMMENCEMENT OF CONSTRUCTION IF NOT SUPPLIED.
- GRASS AND TOPSOIL SHALL BE STRIPPED TO A DEPTH OF 50mm OVER THE EXTENT OF THE WORKS UNLESS DIRECTED OTHERWISE AND STOCKPILED FOR FUTURE USE AS NON-STRUCTURAL FILL IF REQUIRED.
- ANY PROPOSED RETAINING WALL WORKS MUST BE WHOLLY WITHIN THE PROPERTY BOUNDARY OF THE SUBJECT SITE, INCLUDING REAR OF RETAINING WALL DRAINAGE INFRASTRUCTURE FOR RETAINING WALLS IN CUT.
- ALL NEW WORKS TO MATCH NEATLY INTO EXISTING
- ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH APPROVED MANAGEMENT PLANS.
- EARTHWORKS LEVELS WITHIN VERGES SHOWN ARE FINISHED EARTHWORKS SURFACE LEVELS INCLUSIVE OF 100mm TOPSOIL LAYER. EARTHWORKS LEVELS WITHIN LOTS ARE FINISHED EARTHWORKS LEVELS AND EXCLUDES TOPSOIL. EARTHWORKS LEVELS WITHIN ROAD CARRIAGEWAYS ARE ROAD BOX OUT LEVELS. REFER ROADWORKS AND DRAINAGE PLANS FOR FINISHED SURFACE LEVELS.
- CONTRACTOR TO ENSURE SUITABLE EROSION CONTROL MEASURES ARE INSTALLED INCLUDING BUT NOT LIMITED TO SHAKE DOWNS, SILT FENCE ETC.
- PRIOR TO THE CONTRACTOR COMMENCING ANY WORKS DETAILED ON THIS DRAWING, THE CONTRACTOR IS TO NOTIFY ADG ENGINEERS (AUST) PTY LTD AND RECEIVE WRITTEN CONFIRMATION THAT WORKS CAN COMMENCE
- ADEQUATE SAFETY FENCING/BARRIERS TO BE APPLIED TO ALL BATTERS OR RETAINING WALLS (TEMPORARY OR PERMANENT) AS PER RELEVANT AUSTRALIAN STANDARDS AND LEGISLATION.
- DUST CONTROL MEASURES ARE TO INCLUDE SPRAYING WATER ON UNPAVED ROADS, ACCESS TRACKS AND STOCKPILES AT A SUFFICIENT LEVEL TO SUPPRESS DUST GENERATION. ADDITIONALLY CONTRACTORS ARE TO COVER OR ENCLOSE STOCKPILES WHERE REASONABLY PRACTICAL TO RESTRICT DUST MOVEMENT.
- FOR DETAILED GEOTECHNICAL INFORMATION, REFER TO GEOTECHNICAL INVESTIGATION REPORT BY SMEC DATED MARCH 2015. IT IS RECOMMENDED THAT THE GEOTECHNICAL CONSULTANT BE CONTACTED TO CONFIRM THE SOIL CONDITIONS PRIOR TO EARTHWORKS COMMENCING.
- ALL BATTERS AT FRONT OF LOTS TO BE 1 IN 6, UNLESS NOTED OTHERWISE. ALL BATTERS TO REAR AND SIDE BOUNDARIES WITHIN PRIVATE PROPERTIES TO BE 1 IN 2, UNLESS NOTED OTHERWISE.
- CLEARED VEGETATION IS TO BE MULCHED AND STOCKPILED FOR RESPREADING AS DIRECTED BY THE SUPERINTENDENT.
- FOLLOWING THE COMPLETION OF EARTHWORKS THE CONTRACTOR IS TO RESPREAD TOPSOIL AS DIRECTED BY THE SUPERINTENDENT.
- THE CONTRACTOR IS TO LIMIT THE MOVEMENT OF EQUIPMENT AND MANPOWER TO THE MINIMUM AREA NECESSARY FOR EARTHWORKS AND PROTECT ALL VEGETATION OUTSIDE OF THE WORKS BOUNDARY.
- MAXIMUM BATTER SLOPES TO BE 1(V) : 2(H) AS PER SMEC GEOTECHNICAL INVESTIGATION REPORT DATED MARCH 2015.

OVERALL LAYOUT PLAN
SCALE 1:500

ISSUED FOR
CONSTRUCTION

Rev	Date	Description	JMB	SW
0	24.06.19	ISSUED FOR CONSTRUCTION		

0 10 20 30m
SCALE 1:500
AT ORIGINAL SIZE (A1)



ADG
Darwin Office
Tenancy 3, Level 1, 5 Edmunds Street,
Darwin, Northern Territory 0800, Australia
GPO Box 2422, Darwin, Northern Territory 0801
T 1300 657 402 F +617 3871 2266
E info@adgce.com W www.adgce.com
BRISBANE / DARWIN / GOLD COAST / MELBOURNE / PERTH /
SUNSHINE COAST / SYDNEY / TOOWOOMBA

Client COSTOJIC PTY LTD	Discipline CIVIL	Status CONSTRUCTION	Title EARTHWORKS OVERALL LAYOUT PLAN
Project Name ZUCCOLI ASPIRE STAGE 6A CIVIL WORKS	Designed By TM	Checked By SW	Approved By CJM
	Project No. 20696	Drawn By JMB	Scale at A1 1:500
The concepts and information contained in this document are the copyright of ADG Engineers (Aust) Pty Ltd. Use or copying of the document in whole or in part without the written permission of ADG Engineers (Aust) Pty Ltd constitutes an infringement of copyright. Do not scale drawings. If in doubt, ask!			Drawing No. 6A_200
			Revision 0